

NOTES:

1. DO NOT SCALE FROM PRINT.
2. CONTRACTOR TO CHECK & VERIFY DRAWINGS, & TO REPORT ANY DISCREPANCIES TO OWNER BEFORE PROCEEDING WITH ANY WORK.
3. CONCRETE COMPRESSIVE STRENGTH TO BE 30MPa AT 28 DAYS.
4. CONCRETE MATERIALS AND METHODS OF CONCRETE CONSTRUCTION TO MEET LATEST EDITION OF THE C.S.A. STANDARD A23.1 & A23.2.
5. FOOTINGS TO REST ON UNDISTURBED SOIL HAVING AN ALLOWABLE BEARING CAPACITY OF 200 kPa.
6. ALLOW CONCRETE TO REACH DESIGN STRENGTH BEFORE COMMENCING BACKFILLING OPERATIONS.
7. METHODS OF CONSTRUCTION TO MEET LATEST STANDARD OF THE NATIONAL BUILDING CODE OF CANADA.
8. ALTHOUGH THESE DRAWINGS HAVE BEEN CAREFULLY DRAWN AND CHECKED, THE DESIGNERS HOLD ABSOLUTELY NO RESPONSIBILITY OR LIABILITY OF ANY KIND.




REAR ELEVATION




FRONT ELEVATION



OWNER:	
6 UNIT APT BUILDING	
SHEET TITLE:	
FRONT & REAR ELEVATIONS	
SCALE: AS NOTED	DATE: NOV. 2023
DRAWN: A.C.	SHEET 5 OF 9
CHECKED: A.C.	JOB. NO:
APPROVED: BY OWNERS	PROJECT NO:



RIGHT SIDE ELEVATION



LEFT SIDE ELEVATION

NOTES:

1. DO NOT SCALE FROM PRINT.
2. CONTRACTOR TO CHECK & VERIFY DRAWINGS, & TO REPORT ANY DISCREPANCIES TO OWNER BEFORE PROCEEDING WITH ANY WORK.
3. CONCRETE COMPRESSIVE STRENGTH TO BE 30MPa AT 28 DAYS.
4. CONCRETE MATERIALS AND METHODS OF CONCRETE CONSTRUCTION TO MEET LATEST EDITION OF THE C.S.A. STANDARD A23.1 & A23.2.
5. FOOTINGS TO REST ON UNDISTURBED SOIL HAVING AN ALLOWABLE BEARING CAPACITY OF 200 kPa.
6. ALLOW CONCRETE TO REACH DESIGN STRENGTH BEFORE COMMENCING BACKFILLING OPERATIONS.
7. METHODS OF CONSTRUCTION TO MEET LATEST STANDARD OF THE NATIONAL BUILDING CODE OF CANADA.
8. ALTHOUGH THESE DRAWINGS HAVE BEEN CAREFULLY DRAWN AND CHECKED, THE DESIGNERS HOLD ABSOLUTELY NO RESPONSIBILITY OR LIABILITY OF ANY KIND.



OWNER: 6 UNIT APT BUILDING	
SHEET TITLE: LEFT & RIGHT SIDE ELEVATIONS	
SCALE: AS NOTED	DATE: NOV. 2023
DRAWN: A.C.	SHEET 6 OF 9
CHECKED: A.C.	JOB. NO:
APPROVED: BY OWNERS	PROJECT NO: